



Electrotechnical Engineering and Production, joint-stock company
619 00 BRNO, Videaňská 117

REPORT OF PERFORMANCE No: 83 - 0110

Protective current transformer




A handwritten signature in black ink, appearing to read 'J. Janda', written over a horizontal dotted line.

Brno 3th December 1996

Warning: Publication of the contents of this report is not permitted without agreement of the person who has ordered the test.
The report can be reproduced only as a whole and with the written agreement of the testing laboratory.

REPORT OF PERFORMANCE No: 83 -0110		Page: 2
Subject of test: Protective current transformer		Total of pages: 8
Type: CTS 12.S	Kind of test: routine	
	Tested according to: IEC Publications 185	
Rates values:	Test ordered by:	
Rated primary current 400 A	KPB INTRA, s.r.o.	
Rated secondary current 5 A	Fučíkova 860	
Highest voltage for equipment 12 kV	685 01 Bučovice	
Accuracy class 5P	No. of orderer:	
Accuracy limit (n) 5	KPB INTRA 55/96	
Rated output 30 VA	Survey numbers of samples:	
Rated frequency 50 Hz	370-375/96	
Rated dynamic current 125 kA	Atmospheric conditions:	
Rated short-time thermal current 50 kA	Temperature: 20 °C	
Test voltage 28 kV	Pressure:	
	Air moisture:	
Products producer:	Report contains:	Distribution:
KPB INTRA, s.r.o.	sheets of text: 7	KPB INTRA 2x
Fučíkova 860	tables:	IVEP 3x
685 01 Bučovice	oscillograms:	
	diagrams:	
Samples delivered on:	drawings:	
the 18. November, 1996	photographs:	
Result of the test:		
The protective current transformer complies with tests required according to IEC Publications 185.		
date of the test: 19.-21.11.1996	Tested by: <i>Vlastimil Rada</i> Vlastimil Rada	Chief of test rooms: Jaromír Mudra



	REPORT OF PERFORMANCE No.: 83-0110	Page: 3
	Subject of test: Protective current transformer	Total of pages: 8

Results of routine tests of protective instrument
current transformer
Production No.: 1200035

Kind of test	Reached values
Verification of terminal markings acc. to clause 16	Satisfactory
Tests for accuracy acc. to clause 38	Winding: 30 VA class: 5P Satisfactory
Composite error (ϵ) and accuracy limit (n) acc. to clause 40	Winding : $\epsilon \leq 5\%$ $n = 5$ Satisfactory
Power-frequency test on primary winding acc. to clause 17	28 kV - 50 Hz - 1 min Satisfactory
Power-frequency tests between sections of primary and second- ary windings and on secondary windings acc. to clause 18	3 kV - 50 Hz - 1 min Satisfactory
Interturn insulation test acc. to clause 19	100% I_n - 50 Hz - 1 min Satisfactory
Partial discharge acc. to clause 17	$Q < 50$ pC Satisfactory

The protective transformer complies with required according to
IEC Publications 185.

	REPORT OF PERFORMANCE No.: 83-0110	Page: 4
	Subject of test: Protective current transformer	Total of pages: 8

Results of routine tests of protective instrument
current transformer
Production No.: 1200036

Kind of test	Reached values
Verification of terminal markings acc. to clause 16	Satisfactory
Tests for accuracy acc. to clause 38	Winding: 30 VA class: 5P Satisfactory
Composite error (ϵ) and accuracy limit (n) acc. to clause 40	Winding : $\epsilon \leq 5\%$ $n = 5$ Satisfactory
Power-frequency test on primary winding acc. to clause 17	28 kV - 50 Hz - 1 min Satisfactory
Power-frequency tests between sections of primary and secondary windings and on secondary windings acc. to clause 18	3 kV - 50 Hz - 1 min Satisfactory
Interturn insulation test acc. to clause 19	100% I_n - 50 Hz - 1 min Satisfactory
Partial discharge acc. to clause 17	$Q < 50$ pC Satisfactory

The protective transformer complies with required according to IEC Publications 185.

	REPORT OF PERFORMANCE No.: 83-0110 Subject of test: Protective current transformer	Page: 5
		Total of pages: 8

Results of routine tests of protective instrument
current transformer
Production No.: 1200037

Kind of test	Reached values
Verification of terminal markings acc. to clause 16	Satisfactory
Tests for accuracy acc. to clause 38	Winding: 30 VA class: 5P Satisfactory
Composite error (ϵ) and accuracy limit (n) acc. to clause 40	Winding : $\epsilon \leq 5\%$ $n = 5$ Satisfactory
Power-frequency test on primary winding acc. to clause 17	28 kV - 50 Hz - 1 min Satisfactory
Power-frequency tests between sections of primary and secondary windings and on secondary windings acc. to clause 18	3 kV - 50 Hz - 1 min Satisfactory
Interturn insulation test acc. to clause 19	100% I_n - 50 Hz - 1 min Satisfactory
Partial discharge acc. to clause 17	$Q < 50$ pC Satisfactory

The protective transformer complies with required according to IEC Publications 185.

	REPORT OF PERFORMANCE No.: 83-0110	Page: 6
	Subject of test: Protective current transformer	Total of pages: 8

Results of routine tests of protective instrument
current transformer
Production No.: 1200038

Kind of test	Reached values
Verification of terminal markings acc. to clause 16	Satisfactory
Tests for accuracy acc. to clause 38	Winding: 30 VA class: 5P Satisfactory
Composite error (ϵ) and accuracy limit (n) acc. to clause 40	Winding : $\epsilon \leq 5\%$ $n = 5$ Satisfactory
Power-frequency test on primary winding acc. to clause 17	28 kV - 50 Hz - 1 min Satisfactory
Power-frequency tests between sections of primary and secondary windings and on secondary windings acc. to clause 18	3 kV - 50 Hz - 1 min Satisfactory
Interturn insulation test acc. to clause 19	100% I_n - 50 Hz - 1 min Satisfactory
Partial discharge acc. to clause 17	$Q < 50$ pC Satisfactory

The protective transformer complies with required according to IEC Publications 185.

	REPORT OF PERFORMANCE No.: 83-0110 Subject of test: Protective current transformer	Page: 7
		Total of pages: 8

Results of routine tests of protective instrument
current transformer
Production No.: 1200039

Kind of test	Reached values
Verification of terminal markings acc. to clause 16	Satisfactory
Tests for accuracy acc. to clause 38	Winding: 30 VA class: 5P Satisfactory
Composite error (ϵ) and accuracy limit ($n \%$) acc. to clause 40	Winding : $\epsilon \leq 5 \%$ $n = 5$ Satisfactory
Power-frequency test on primary winding acc. to clause 17	28 kV - 50 Hz - 1 min Satisfactory
Power-frequency tests between sections of primary and second- ary windings and on secondary windings acc. to clause 18	3 kV - 50 Hz - 1 min Satisfactory
Interturn insulation test acc. to clause 19	100% I_n - 50 Hz - 1 min Satisfactory
Partial discharge acc. to clause 17	$Q < 50$ pC Satisfactory

The protective transformer complies with required according to
IEC Publications 185.

	REPORT OF PERFORMANCE No.: 83-0110 Subject of test: Protective current transformer	Page: 8 Total of pages: 8
Results of routine tests of protective instrument current transformer Production No.: 1200040		
Kind of test	Reached values	
Verification of terminal markings acc. to clause 16	Satisfactory	
Tests for accuracy acc. to clause 38	Winding: 30 VA class: 5P Satisfactory	
Composite error (ϵ) and accuracy limit (n) acc. to clause 40	Winding : $\epsilon \leq 5\%$ $n = 5$ Satisfactory	
Power-frequency test on primary winding acc. to clause 17	28 kV - 50 Hz - 1 min Satisfactory	
Power-frequency tests between sections of primary and secondary windings and on secondary windings acc. to clause 18	3 kV - 50 Hz - 1 min Satisfactory	
Interturn insulation test acc. to clause 19	100% I_n - 50 Hz - 1 min Satisfactory	
Partial discharge acc. to clause 17	$Q < 50$ pC Satisfactory	
The protective transformer complies with required according to IEC Publications 185.		